

**SCHEDULE OF RATES (SOR) -
PRICE BID ON ANNUAL RATE CONTRACT (ARC) FOR STRUCTURAL PAINTING JOBS
TENDER REF: ISPRL/VSP/PR-08/17-18/Str Paint-ARC/ T6 dated 30.10.2017**

SL.NO	DESCRIPTION	UNIT	TOTAL QTY	RATE/UNIT, ₹	TOTAL AMOUNT, ₹
1	SURFACE CLEANING : Cleaning of the surface thoroughly by removing flakes, oil, dust deposits, vegetation growth, moss, pasted paper, posters etc., using coir / coil brush, emery / sand paper and water washing, if required as instructed by the Engineer-in-charge so as to enable the application of respective primer etc., at all heights and depths including the necessary scaffolding, ladders, ropes, brushes, manpower with supervision etc., complete.	sq.m	8000.0		
2	PRIMER PAINTING OF TANKS/PIPES/PIPE RACKS/EQUIPMENT : Applying two coats each of approved quality/make/ ZINC primer paint complete incl. cost of Paint and application at all heights and depths including the necessary scaffolding, ladders, ropes, brushes, manpower with supervision etc., complete.	sq.m	8000.0		
3	PRIMER PAINTING OF TANKS/PIPES/PIPE RACKS/EQUIPMENT : Supply and Application of Two coats of Epoxy paint (sea blue,post office red , green or any other colour as specified) incl. cost of Paint and application at all heights and depths including the necessary scaffolding, ladders, ropes, brushes, manpower with supervision etc., complete.	sq.m	8000		
4	Normal Paint Stenciling Charges : Stenciling on pipes/tanks/walls / cabins/panels etc as per the directions of Engineer in-charge which includes preparation of base	Inches	90000		
5	Radium Stickers : Supply and fixing of Radium stickers on the metallic boards as directed by Engineer in-charge	Sq. Inches	15000		
6	Painting of Sign Boards, Logos & Slogans : Cleaning of the surface, preparation of base for carrying this job with necessary men,material etc	Sq.m	40		
				Sub - Total (A), ₹	
				GST 18% (B), ₹	
GRAND TOTAL AMOUNT, ₹ (in figs) {(A) + (B)}					
GRAND TOTAL AMOUNT, ₹ (in words)					