

**SCHEDULE OF RATES (PRICE BID)**  
**TENDER NO. ISPRL/VSP/RCC ROAD LAYING TO HILL TOP /T9/16 dated 28.12.2016**

S No	Description	Quantity	Unit	Rate	Amount	Remarks
<b>A) Road work</b>						
1	a) Earth work in surface excavation not exceeding 200 mm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed :	4216.00	sqm			
2	Providing minimum 100 mm thick Plain Cement Concrete (1:4:8) mix using 40mm size HBG crushed stone aggregate and fine aggregate conforming to table 1000-2 of MoRT&H including cost, seigniorage conveyance of all materials to site and labour charges, centering, machine mixing, laying, Vibrating, curing and seigniorage charges, all taxes etc., complete for filling foundations	421.00	Cu m			
3	Providing 180 mm thick Cement Concrete M20 grade (Design Mix) with minimum quantity of cement 310 Kg using 20mm down graded machine crushed granite chips from approved quarry confirming to table 1000.1 of MORT&H specn. for coarse aggregate and table 1000.2 of MORT&H specn. for fine aggregate including cost and conveyance of all materials (Viz) cement, sand, stone aggregate, water etc., to site , seigniorage charges, centering,shuttering, machine mixing, laying concrete, vibrating, finishing smooth to required levels, curing, all other incidental and operational charges, labour charges, all taxes, etc.,complete for Wearing Coat, as perMORTH specification 1500,1700&2200 (C)(using concrete mixer) - Foot paths etc...	500.00	Cu m			
4	Supplying & providing Tor steel reinforcement (Grade Fe-415) and put up including decoiling, bending, cranking and tying them after placing in position as directed by Engineer-in-Charge including cost and conveyance of steel and binding wire, all taxes, labour charges for all operations etc., complete	15.76	MT			
5	Supply & filling useful gravel for road levelling in down area and for laying the shoulder on both sides as per direction of engineer-in-charge,filling gravel, leveling ,watering..etc completed work on site,( the excavated rock gravel cannot be counted)	394.00	Cu m			
6	Supply, delivery and fixing of Mastic Pads of 25.40 mm thick including cost and conveyance and labour charges etc., complete for expansion joints.including cutting and placement....(each mastic pad placed for ever 4.5mts length)	125.00	no of joints			
7	PVC pipe 160mm dia 6 kg/mm <sup>2</sup>	18	Rm			
<b>B) Drain works</b>						
8	Brick work in Cement Mortor 1:6	10.8	Cu m			
9	Plastering with CM (1:5) prop 12mm thick using best sand including seigniorage, all taxes, cost and conveyance of all materials to site, labour charges for all operations including curing etc., complete.	100	sqm			
<b>TOTAL (Rs.) (in figs)</b>						
<b>TOTAL (Rs.) (in words)</b>						

The quantities given in this Schedules of Rates under Quantities are tentative and the quantities may increase/decrease as per the site conditions. (The above rates includes all applicable taxes & services)

(Signature of bidder with seal)